BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work:Improvements & Construction of CC Road From Katarayananagar to Manjunathanagara Via Coconut Garden in Ward No.14.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	54.00	81.00	Rupees Eighty One Only
2	Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	106.50	1059.48	Rupees One Thousand Fifty Nine and Forty Eight Paise Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	114.60	3812.82	Rupees Three Thousand Eight Hundred Twelve and Eighty Two Paise Only
4	Providing and laying in position plain cement concrete of design mix M20 with OPC cement @320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reafirmed-2008, machine mixed, concrete laid in layers not blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	106.98	5142.06	Rupees Five Thousand One Hundred Forty Two and Six Paise Only
5	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	46.44	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only

Signature of the Contractor
Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer

6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	135.00	239.56	Rupees Two Hundred Thirty Nine and Fifty Six Paise Only
7	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	45.00	1600.00	Rupees One Thousand Six Hundred Only
8	Lead for Disposal of Debris shall be payable at carage rates be mechanical means - With all lead, lifts, loading and unloading charges, cost and conveyance of all matrials, labour, equipments - 10Kmtrs etc. complete as per specifications.	Cum	54.00	78.24	Rupees Seventy Eight and Twenty Three Paise Only
9	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, c10ser blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	52.00	683.70	Rupees Six Hundred Eighty Three and Seventy Paise Only
10	Vaccum de-watering with vaccum pump and suction mat and compaction wath skin floater clubbed with floating disc including cost of generator, HOM of machinery, screned vibratory, power floater, blade and disc., with all lead and lift. complete as per specifications.	Sqm	710.00	84.80	Rupees Eighty Four and Eighty Paise Only
11	Providing and fixing in position 20 mm thick premoulded joint filler in expansion joint for fixed ends of simply supported spans not exceeding 10 m to cater for a horizontal movement upto 20 mm, covered with sealant complete as per drawing & Technical Specification complete as per specifications.	M	75.00	167.48	Rupees One Hundred Sixty Seven and Forty Eight Paise Only

Signature of the Contractor
Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division,